Abstract Notification, dated 7th November 1933.

SUBJECT:—Constructing a Town Hall at Madhugiri.

Attention of the public is drawn to notification calling for tenders for the above work in pages 1448 and 1449 of Part VI of the *Mysore Gazette*, dated 16th November 1933.

2. The tenders will be received by the Executive Engineer, Tumkur Division, Tumkur up to 2 P.M. of 4th December 1933.

3. An earnest money of Rs. 750 should accompany the tender.

Abstract Notification, dated 7th November 1933.

SUBJECT:—Constructing a Masonry Anicut across the left weir channel of Doddanitta. gunta tank, Gubbi Taluk.

Attention of the public is drawn to notification calling for tenders for the above work in pages 1450 and 1451 of Part VI of the *Mysore Gazette*, dated 16th November 1933.

2. The tenders will be received by the Executive Engineer, Tumkur Division, Tumkur up to 2 P.M. of 11th December 1933.

3. An earnest money of Rs. 200 should accompany the tender.

N. G. KRISHNA IYENGAR,
Executive Engineer.

MYSORE DIVISION.

Abstract Notification, dated 29th—31st October 1933.

The attention of the public is invited to the detailed notification, published in page 1408 of Part IV of the *Mysore Gazette* regarding the auction sale of old Police Site at Hunsur. The date of auction is 30th November 1933.

V. V. PATANKAR,
Executive Engineer.

MYSORE RAILWAYS DIVISION, MYSORE.

Abstract Notification, dated 10th November 1933.

The attention of the public is invited to the detailed notification of 4th November 1933, regarding the earthwork to be done in Central Workshops area, published in pages 1406 and 1407 of Part VI of the *Mysore Gazette*, dated 9th November 1933.

Last date of receiving tenders is 25th November 1933 (4 P.M.).

MYSORE DIVISION (OPEN LINES).

Notification, dated 17th November 1933.

Notice is hereby given that sealed tenders will be received at the Office of the Senior Executive Engineer, Open Line Division, Mysore Railways, Mysore up to 4 P.M. on the 11th December 1933, from Contractors who are willing to do the work of construction of an additional stores building 40' x 20' in the Central Workshops area at Mysore.

2. Every tender must be accompanied by an earnest money of Rs. 150, which should be paid to the Auditor, Mysore Railways, Mysore and the receipt thereof enclosed along with the tender.

3. Tenders should be submitted in special forms which can be obtained from the Senior Executive Engineer, Mysore Railways, Mysore on payment of rupee one, which amount is not refundable under any circumstances.

4. Tenders which give rates, as per estimate rates or so much per cent above or below estimate rates will not be considered. The rates should be noted both in figures and words.

5. The name of the accepted tenderer will be posted on the Notice Board of the Senior Executive Engineer's Office as soon as it is approved by the Superintendent, Way and Works, Mysore Railways, Mysore. No enquiries regarding the acceptance or rejection of a tender will be replied.

6. The earnest money of the unsuccessful tenders will be returned as soon as possible after the tenders are disposed of while that of the successful tenderer will be accepted as part payment towards the security deposit due as per para 7 *infra*.

7. The successful tenderer should deposit with the Auditor, Mysore Railways, Mysore before he signs the schedule agreement, five per cent of the value of the work for which the tender is accepted as security for due fulfilment of the terms of the agreement.

8. The final acceptance of the tender will rest with the Superintendent, Way and Works, Mysore Railways, Mysore, who does not bind himself to accept the lowest or any tender and who further reserves to himself the right to reject, without assigning any reasons thereof, any or all the tenders.

9. Successful tenderers should execute within eight days of the date of notification of acceptance of tenders, the usual Railway Schedule Agreement. Failure to comply with this condition will render the contract null and void and the earnest money forfeited.

10. Work should be started within two weeks from the date of acceptance of tender and completed within four months with a guaranteed monthly rate of progress. The accompanying schedule gives the approximate quantity of works and this quantity is not guaranteed.

11. The time limit specified in para 10 should be strictly adhered to and any violation of this will render the contractor liable to forfeit his five per cent. deposit amount not as a penalty but as ascertained and liquidated damages recoverable accordingly.

12. Plans and specifications and other details of work to be done are available for inspection in the Senior Executive Engineer's Office, Mysore Railways, Mysore, where intending tenderers may call and obtain required information during office hours.

13. In all matters of dispute regarding rates, measurements, quality of work, etc., and in all disputes of any kind, the decision of the Superintendent, Way and Works, Mysore Railways, Mysore, will be final and legally binding.

14. Contractors should make their own arrangements for water required for the work and departmental water will not be supplied.

15. Specification for works will be according to Murryat's Hand Book, Vol. I.

Schedule.

No.	Particulars	Per	Quantity
1	Earthwork, excavation in all soils including hard rock ...	1,000 C.ft.	1,200 C.ft.
2	Concrete, broken stone in and mortar ...	100 C.ft.	370 C.ft.
3	Coursed rubble masonry, first sort, in sand mortar including bond stones and dressing corner stones.	Do	1,000 C.ft.
4	Burnt brick in sand mortar ...	Do	2,400 C.ft.
5	Burnt stone slabs 6" thick, dressed and fixed in mortar...	Sq. ft.	240 Sq.ft.
6	Teak-wood doors with 1½" thick, battened shutters as per approved design.	Do	48 Sq.ft.
7	Teak-wood windows with 1" thick, battened shutters inside and 1" diameter iron bars and expanded metal shutters outside as per approved design.	Do	156 Sq.ft.
8	Cement concrete bed blocks for trusses including fixing of holding down bolts.	C.ft.	24 C.ft.
9	Hoisting, and fixing steel trusses of 20 feet span, in position.	Each	4
10	Teak-wood wrought and put up including two coats of wood oiling.	C.ft.	98 C.ft.
11	Hoisting, and fixing in position cantilever brackets including fixing of bolts in walls.	Each	6
12	Roofing with first class Mangalore pattern roofing tiles over 2" x 1" teak reepers including chunam borders, etc., complete with R. M. C. for tiles.	100 Sq. ft.	1,800 Sq.ft.
13	Ridge tiles set in mortar and cement pointing ...	R.ft.	46 R.ft.
14	Chunam pointing	100 Sq.ft.	200 Sq.ft.
15	Chunam plastering	Do	3,300 ,,
16	White and colour washing	Do	3,500 ,,
17	Silicate chocolate painting	Do	1,000 ,,
18	Flooring with 4" thick burnt stone slabs two lines dressed over 6" thick concrete (broken stone in sand mortar) bed including cement pointing.	Do	1,088 ,,
19	Teak-wood sunshades as per approved design ...	Each	11

OFFICE OF THE SENIOR EXECUTIVE ENGINEER, MYSORE RAILWAYS, MYSORE.

Abstract Notification, dated 12th November 1933.

The attention of the public is invited to the detailed notification calling for tenders for executing "Earthwork" in the Mysore Railways Central Workshops area at Mysore, published in pages 1406 and 1407, Part VI of the *Mysore Gazette*, dated 9th November 1933.

R. N. MIRZA,